PACKAGE No-04 Construction of Classrooms to Govt PU College and providing grill fencing and Other developmental Works to ISRO layout Park, Vishweshwarayya park, Raj kumar Park, Sri Saibaba park Yelahanka Assembly Constituency Under Amrutha Nagarothana Grants

Calculation Sheet for Dismentling Fencing

Sl No	Discription	Length of existing available Chain link fencing in Mtrs	Details	Weightin Kg/mt/Sqm	Quantity in Kgs	Rate /Kg	Amount in Rs.
1	Fencing Pole (65x65x6)mm Equal angle		Angle Length inMtrs				
	Vishveshwaraiah park	148.92	297.84	5.80	1727.45	22.00	38003.87
	Sai baba (Cauvery) Park	84.63	169.27	5.80	981.75	22.00	21598.47
2	Fencing Pipe 14 guage (Aclass 40mm Pipe)		Nos of Pipes				
	Vishveshwaraiah park	148.92	2	3.20	953.08	22.00	20967.65
	Sai baba (Cauvery) Park	84.63	2	3.20	541.65	22.00	11916.40
3	Fencing Mesh		Height of Mesh				
	Vishveshwaraiah park	148.92	1.20	4.57	816.67	22.00	17966.66
	Sai baba (Cauvery) Park	84.63	1.20	4.57	464.13	22.00	10210.86
				Total in Rs.			120663.92

Assistant Engineer
Project Division Yelahanka

Asst. Executive Engineer
Project Division Yelahanka

Scanned by TapScanner